



PCB box and Operation switch

| | |
|----------------------------|---------------------------|
| Voltage | AC100V~120V |
| Frequency | 50Hz/60Hz |
| Current | 0.96A |
| Motor rated operation time | 4min |
| Travel speed | 50Hz:83 60Hz:100 (mm/sec) |

| | |
|------------------|---|
| Screen materials | Pure MatIII Cinema (WF302) |
| Screen case | Symmetry case |
| Front panel | Color: Black Detachable |
| Mechanism | Tension adjustment, side tension method |
| Weight | 15.5Kg |
| Accessory | IR Remote controller Transmitter/Receiver x1 Sliding Bracket x2 Side Bracket x1 set Truss tapping screws with cross hole(4x40) x6 Truss tapping screws with cross hole(4x12) x4 |
| Option | Wall switch(S-R2) |

Note

- The switch box, the primary and secondary electric wirings, plumbings and wiring materials are required separately.
- The reception sensitivity may decrease and IR range may be shortened under the inverter lighting.
- External dimensions are rounded up after the decimal point.
- *Size shown is with side bracket.